



REPORT GENERATED	DECISION AS OF	REQUIRED ARRIVAL	MARKET DATA DATE
14 Sep 2026, 04:05 PM IST	2025-03-31	2027-02-09	2025-03-31 (BDI)

VOYAGE PARAMETERS & NOMINATION		DECISION SNAPSHOT	
ORIGIN PORT (LOADING)	Australia (Hay Point, QLD)	RECOMMENDED ACTION	WAIT
DESTINATION PORT	PARADIP Max Draft: 14.5m LOA: 260m Wait: 1.8d	OPTIMAL VESSEL	PANAMAX
CARGO REQUIREMENT	75,000 MT Metallurgical Dry-Bulk Coal	OVERALL RISK	52 / 100 (MEDIUM)
REQUIRED ARRIVAL DATE	2027-02-09	TOTAL VOYAGE COST	\$656,286
RECOMMENDED VESSEL	PANAMAX (82,000 DWT)	COST PER MT	\$8.75 / MT Rs. 747.6/MT
TRANSIT & SEAWAY TIME	~19.9 sea days @ 13.0 kn	MARKET AS OF	2025-03-31

CHARTERING ADVISORY: WAIT — (datetime.date(2025, 6, 25), datetime.date(2025, 7, 3))

Expected low of -28.3% around 2025-06-29; upper band stays close to today's level, so waiting is low-regret. Evaluated against physical berth dimensions, real-time marine weather, TCE voyage costs, and multi-horizon market trajectory.

KEY DECISION FACTORS & ENGINEERING RATIONALE

• 1 voyage(s) of ~77,900 MT capacity; utilisation 96%.
• Port limits (LOA, beam, DWT, draft) satisfied.
• Estimated total cost \$8.75/MT vs Supramax \$11.95/MT (+3.20).
• Timing: WAIT — Expected low of -28.3% around 2025-06-29; upper band stays close to today's level, so waiting is low-regret.
• Expected port wait 1.8 days; overall risk 52/100 (MEDIUM).



VOYAGE ECONOMICS & TIME-CHARTER EQUIVALENT (TCE) COST BREAKDOWN

Expense Category	Operational Basis / Activity Days	Amount (USD)	Amount (INR)
Vessel Time Charter Hire	21.7 active days @ \$9,682/day	\$239,592	Rs. 20,468,305
Bunker Fuel (Base Transit)	Laden sea leg + 50% ballast allocation	\$305,803	Rs. 26,124,767
Weather Fuel Adjustment	0.0 extra days / sea-state speed loss	\$0	Rs. 0
Port Discharging Charges	Terminal tariff at Paradip	\$90,000	Rs. 7,688,700
Berth Waiting & Demurrage	Estimated 1.8 waiting days at anchorage	\$20,892	Rs. 1,784,770
TOTAL LANDED VOYAGE COST	Complete Landed Expenditure	\$656,286	Rs. 56,066,541
FREIGHT COST PER METRIC TONNE	Cargo: 75,000 MT landed	\$8.75 / MT	Rs. 747.6 / MT

MULTI-FACTOR RISK ASSESSMENT	
Market Volatility	100 / 100
Fuel Price Momentum	58 / 100
Port Congestion Risk	30 / 100
Weather Operational	20 / 100
OVERALL COMPOSITE	52 / 100 (MEDIUM)

FREIGHT INDEX FORECAST (BDI / BCI / BPI)		
Horizon	Expected	80% Conformal Range
7 Days	1,220 pts	[1,113 – 1,337]
14 Days	1,291 pts	[1,101 – 1,514]
30 Days	1,777 pts	[1,481 – 2,131]
60 Days	1,501 pts	[1,170 – 1,925]
90 Days	1,076 pts	[841 – 1,376]

VESSEL & DISCHARGE PORT ENGINEERING COMPLIANCE

Technical Parameter	Nominated Vessel (Panamax)	Berth Limit (Paradip)	Compliance Status
Deadweight Tonnage (DWT)	82,000 MT	Max 125,000 MT	FEASIBLE
Maximum Arrival Draft	14.4 m (Design)	Max 14.5 m Permissible	CLEARED
Length Overall (LOA)	229 m	Max 260 m	CLEARED
Beam (Width)	32.3 m	Max 45 m	CLEARED
Discharge Rate / Turnaround	Standard Cargo Handling	25,000 MT / day	OPERATIONAL

Statutory Verification Protocol: This advisory is generated by Sagar Drishti decision algorithms. Prior to executing a legally binding charter party fixture (BIMCO GENCON / AMWELSH), designated SAIL Chartering Officers must verify the nominated vessel's formal Q88 form against live Notice to Mariners, tidal tables, and local Port Master bulletins. Aligned with the National Steel Policy 2017 and Maritime India Vision 2030.